




"FTR" NORMAL ALONG ROOF CONSTRUCTION




1. The doors are produced to sizes according to actual pricelist KRISPOL.
2. To adjust the picture to selcted size it needs to be accordingly enlarged/reduced.
3. The exact value of Wn by using different types of drives according to actual Krispol price
4. Application of the relevant product is a prerequisite for its proper functioning.
5. To select the optimal solution, please contact your representative of Krispol company ---->>> www.krispol.eu



- DESCRIPTION OF DIMENSIONS:**
- ORB - workspace of the door
 - B - opening width
 - H - opening height
 - Hn - headroom height
 - bk - sideroom width with mounting bracket
 - b min - sideroom width including perforated angles
 - bc - sideroom width on chain mechanism side
 - bn - sideroom width on drive side
 - HP - passage height in the hand-operated door
 - HP+n - passage height in door with drive
 - HR1 - workheight
 - HW - height from the floor to axle shaft
 - W - built-in depth (hand-operated door)
 - Wn - built-in depth (drive-operated door)
 - WC - built-in depth for chain mechanism
 - H1 - height from the floor to the uppr edge of supporting structure
 - Q - curtain's weight [kg/m2]
 - P - area of door's curtain [m2]
 - a - decrease of roof slope

SYMBOL	SIZE LIMIT [mm]			DIMENSIONS ON THE DRAWING [mm]	
B	max.8000			4000	
H	max.3000	max.5510	max.6000	4000	
Hn	min.450	min.450	min.510	450	
HW	H+335	H+357	H+377	4357	
H1	H+405	H+427	H+447	4427	
W	H+340			4340	
bk	min.100			100	
b min	min.140			140	
bc	min.260			260	
bn	min.440			440	
HP	H-50			3950	
HPn	H			4000	
HR1	H-170			3830	
Wn	400			400	
Wc	270			270	
α	5°+35°			30	
P	K2 IS	P=max.32 [m ²]	Q=max.13 [kg/m ²]	16,00[m ²]	208,0 [kg]
	K2 IM	P=max.32 [m ²]	Q=max.13 [kg/m ²]		
Q	K2 IP	P=max.31 [m ²]	Q=max.13 [kg/m ²]	112,0 [kg]	
	K2 IA	P=max.32 [m ²]	Q=max.7 [kg/m ²]		



KRISPOL Sp. z o.o.
ul. Budowlana 1
Psary Małe, 62-300 Września

KRISPOL

INDUSTRIAL SECTIONAL DOOR

"FTR" NORMAL ALONG ROOF CONSTRUCTION

Format A3 Scale 1:50 Type K2 I Drawing No XYZ_K2IS_FTR_4000x4000_2018-8-7